



Lefever Building Systems

*Denver County Jail  
Production Kitchen Facility*  
Denver, Colorado

**Project Fact Sheet**

**Project Location:** 10500 Smith Road, Denver, Co 80239  
**Architect:** Reilly Johnson Architecture  
**General Contractor:** FCI Constructors, Inc.; Longmont, Co  
**Pre-Engineered Metal Building:** VP Buildings  
**Supply & Erection:** Lefever Building Systems  
**Project Time Frame:** July 2008 – December 2008  
**Project Metal Building Subcontract Value:** \$301,976

**Project Overview:**

140' wide x 200' long x 16' high pre-engineered metal building with one corner of building being a 110' wide x 62' long x 32' high taller area. Roof pitch of 1:12 with one row of interior columns.

**Scope:**

Building was erected by Colorado Core and Shell subcontracted by FCI Constructors. Lefever Building Systems subcontracted the roof panel and roof insulation installation from the main building erector. A 34' wide x 20' deep recessed loading dock was included on the north side of the building. Twenty-one roof curbs were supplied and installed for roof top HVAC equipment along with 1 roof access hatch.



**Details on Steel Buildings:**

**Roof Panels:** 24 ga Standing Seam; Color; Galvalume

**Wall Panels:** 26 ga, Panel Rib; Cool Sierra Tan color

**Insulation:** 9 1/2" (R-30) roof and 4" (R-13) wall insulation with WMP-VR facing

**For more info on Lefever Building Systems, call us at 303-297-3494 or go to [www.lefeverbuilding.com](http://www.lefeverbuilding.com)**